



1584 Hadley Avenue N | Oakdale, MN 55128
651-739-5086 | www.ci.oakdale.mn.us

MOBILIZATION (OAKDALE 2021)

PART 1 GENERAL

1.01 SUMMARY

- A. Section includes preparatory Work for construction operations.
- B. Related Sections:
 - 1. Section 2031 – Temporary Sanitary Facilities
- C. Method of Measurement:
 - 1. Measure all required procedures and activities on a Lump Sum basis, except as otherwise noted.
- D. Basis of Payment:
 - 1. If the Lump Sum Bid amount for Mobilization exceeds 5 percent of the total Base Bid amount, the Owner will withhold the amount in excess of 5 percent until Substantial Completion of the Project.
 - 2. Payment for Mobilization shall be at the Contract unit Price as list on the Bid Form. All associated Work items shall be considered incidental.

1.02 REFERENCES

- A. MnDot 2021

1.03 SUBMITTALS

- A. Required Submittals Prior to Mobilization:
 - 1. Approved Project Schedule.
 - 2. Shop Drawing Schedule.
 - 3. List of Proposed Subcontractors.
 - 4. List of Proposed Suppliers.
 - 5. Material and Procedural Submittals as Required.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.01 CONSTRUCTION

- A. Movement of personnel, equipment, supplies, and incidentals to the Site.
- B. Establishment of Contractor offices and facilities.
- C. Installation of temporary sanitary facilities.
- D. Commencement of Work.

END OF SECTION