



1584 Hadley Avenue N | Oakdale, MN 55128  
651-739-5086 | www.ci.oakdale.mn.us

## **TEMPORARY EROSION CONTROL (OAKDALE 2573)**

### **PART 1 GENERAL**

#### **1.01 SUMMARY**

- A. Section Includes:
  - 1. Temporary measures to control soil erosion and sedimentation.
  - 2. Furnishing, installing and maintaining erosion or sediment control devices.
  - 3. Preparation and filling of erosion control plan (SWPPP).
- B. Related Sections;
  - 1. Section 2105 – Excavation and Embankment
  - 2. Section 2451 – Trench Excavation and Backfill
  - 3. Section 2575 – Turf Establishment
- C. Measurement Procedures:
  - 1. Bale Checks: Measure by number of bales furnished and acceptably installed.
  - 2. Silt Fence: Measure by length in linear feet along base of fence from outside to outside of end posts.
  - 3. Bio-roll: Measure by length in linear feet.
  - 4. Storm Drain Inlet Protection: Measure as a lump sum for entire project. Includes furnishing and installing reusable inlet devices for all storm drain inlets within the project area.
    - a. Provide drainage rock and a Bio-roll (Sediment Log) perimeter around Storm structures where the casting has been temporarily removed for structure or curb work. Reinstall Inlet Protection device when curb and casting are re-established.
- D. Payment Procedures:
  - 1. Payment for acceptable quantities of erosion control items shall be at the Contract Unit Price as listed on the Bid Form. All associated Work items shall be considered incidental.

#### **1.02 REFERENCES**

- A. MnDOT 2573 – Storm Water Management
- B. Protecting Water Quality in Urban Areas – Best Management Practices for Minnesota published by the Minnesota Pollution Control Agency

#### **1.03 DEFINITIONS**

- A. BMPs: Best Management Practices

- B. For the NPDES permit process, the operator is defined as the Contractor.
- C. SWPPP: Storm Water Pollution Prevention Plan

#### **1.04 SUBMITTALS**

- A. NPDES Permit MN R100001.
- B. Proposed schedule for accomplishment of Work within, adjacent to, or affecting surface water.
- C. Erosion control schedule.

#### **1.05 REGULATORY REQUIREMENTS**

- A. For operations that disturb 1 acre or more of land area, submit NPDES Application for General Storm Water Permit for Construction Activity (MN R100001).
  - 1. Construction may begin 7 days after application is postmarked or 1 day after online submittal.
  - 2. Complete and attach SWPPP form to NPDES permit.
    - a. SWPPP to be kept at Site.
    - b. SWPPP must be made available to federal, state, and local officials within 72 hours upon request for the duration of the permit and for 3 years following NOT (Notice of Termination).
    - c. Submit NOT within 30 days of final stabilization.
- B. Exposed Soil Areas Adjacent to Surface Water:
  - 1. Provide year-round temporary erosion protection for all exposed soil areas with a continuous positive slope within 200 lineal feet of a surface water.
  - 2. The maximum time these areas can remain open when not actively being worked is as follows:
    - a. 7 days on slopes steeper than 3:1.
    - b. 14 days on slopes between 3:1 and 10:1.
    - c. 21 days on slopes flatter than 10:1.

#### **1.06 QUALITY ASSURANCE**

- A. Refer to "Protecting Water Quality in Urban Areas – Best Management Practices for Minnesota."
- B. Obtain all necessary permits from responsible regulatory agencies.
- C. Ensure minimum interference with roads, streets, walks, and adjacent occupied or used facilities. Do not close or obstruct without permission from authorities having jurisdiction.

### **PART 2 PRODUCTS**

#### **2.01 MATERIALS**

- A. Bale Checks Type 1: MnDOT 3882.

- B. Silt Fence: MnDOT 3886.
- C. Inlet Protection: MnDOT 3891. WIMCO Road Drain Curb and Gutter inlet device, or approved equal.
- D. Bio-Roll Blanket System: MnDOT 3889, Type 3.
- E. Erosion Control Blanket: MnDOT 3885.
  - 1. Category 0; 1S: Wood fiber, rapidly degradable, one side netting.
  - 2. Category 3; 2S: Straw or wood fiber, netting two sides.
  - 3. Category 4; 2S: Straw/coconut or wood fiber, netting two sides.
  - 4. Category 6; 3S: Straw/coconut or wood fiber, netting 2 sides, high velocity.
- F. Erosion Stabilization Mat; MnDOT 3888.
- G. Temporary seed, fertilizer, mulch, and disc anchoring: See Section 2575.
- H. Staples: MnDOT 3888 U-shaped, 11 gage, 8 inches in length.

## **PART 3 EXECUTION**

### **3.01 PREPARATION**

- A. Coordinate erosion control measures with earthwork and turf establishment operations.
- B. Complete grading, finishing, erosion control and turf establishment on a drainage area basis to prevent excessive soil erosion.
  - 1. Shape exposed soil areas to permit runoff with minimal erosion.
- C. Install erosion control measures as directed by Engineer prior to disturbance of in-place ground cover in critical areas tributary to public waters.
- D. Place erosion control materials to prevent siltation either to adjacent property or within boundaries of the Site.
- E. Install safeguards to prevent water pollution from haul roads, work platforms, or other temporary construction facilities.
- F. Minimize sediment from entering surface waters, curb and gutter systems, and storm sewer inlets.
- G. Place erosion control for wetland protection prior to Work on any phase of the Project.

### **3.02 PLACING TEMPORARY EROSION CONTROL ITEMS**

- A. Construct items in conformance with typical sections and elevation controls shown on Drawings.
- B. Hay Bales:
  - 1. Place lengthwise on contour, with ends of adjacent bales tightly abutting.
  - 2. Wrap ends of dike uphill to prevent flow around ends.

3. Bind with wire or nylon string around sides.
  4. Securely anchor with minimum of 2 stakes.
  5. Excavate trench the width of a bale and the length of proposed barrier to a minimum depth of 4 inches. Backfill excavated soil against barrier.
- C. Silt Fence:
1. Place parallel to contour of land, with ends wrapped uphill to prevent flow around them.
  2. Posts:
    - a. 3-inch diameter wood.
    - b. 2-inch by 2-inch square wood.
    - c. 1.33 pounds per linear foot steel "U" or studded tee posts, or material of equivalent strength.
    - d. Minimum length of 5 feet.
  3. Preassembled: MnDOT 3886.
- D. Storm Drain Inlet Control:
1. Install reusable inlet insert in all storm drains within project area unless adjacent to a paved or vegetated surface.
- E. Sediment Traps:
1. Earthen embankment with gravel outlet, across a drainage swale, for drainage area of less than 5 acres.
  2. Construct before rough grading.
  3. Requires 1,800 cubic feet of storage for every acre of drainage area.
  4. Embankment to discharge water through section of crushed stone having a median diameter of 3/4-inch and be 6 feet long per acre of drainage area. Crest of outlet must be 1 foot lower than embankment elevation.
- F. Temporary Diversion:
1. Maximum allowable drainage area is 5 acres.
  2. Supporting ridge must be at least 9 inches high.
  3. Release diverted runoff through stabilized outlet, slope drain, or sediment trapping measure.
  4. Construct at end of each workday as needed.
  5. Locate at least 2 feet inside top edge of fill.
  6. Construct supporting ridge along lower side a uniform height along entire length.
- G. Remove sediment deposits when they reach 1/2 height of barrier. Dispose of sediment as directed by Engineer.
- H. Dust Control: Prevent spread of dust during performance of Work.
- I. Erosion Control Blanket: Install according to manufacturer's recommendations.
- J. Staples: Minimum number of staples to secure blanket:
1. Single net, short term: 0.7 staples per square yard.
  2. Double net, short term: 1.2 staples per square yard.
  3. Double net, extended term: 1.75 staples per square yard.
  4. Turf reinforcement mats; 3.5 staples per square yard.

### **3.03 EMERGENCY EROSION CONTROL**

- A. Upon written order by Engineer, conduct temporary erosion control Work on an emergency basis.
  - 1. Mobilize with sufficient personnel, equipment, materials, and incidentals within 24 hours of receipt of order.
  - 2. Provide immediate corrective work followed by installation of erosion control measures.

### **3.04 REPAIR AND MAINTENANCE**

- A. Inspect, repair, and maintain all erosion control measures to provide proper function throughout Project.
- B. Failure to maintain erosion control measures: Owner may hire another firm to maintain erosion control measures. Costs associated with hiring another firm will be deducted from the Contract.
- C. Silt Fence:
  - 1. Inspect immediately after each runoff event and minimum once daily during prolonged rainfall.
  - 2. Make required repairs immediately.
  - 3. When sediment deposits reach approximately one-half the height of the silt fence, remove sediment or install a second silt fence.
  - 4. Dispose of sediment as directed by Engineer.
- D. Erosion Control Blanket: Immediately repair if washed away or displaced.

### **3.05 FIELD QUALITY CONTROL**

- A. Inspections and maintenance prior to final acceptance;
  - 1. Every 7 days.
  - 2. Within 24 hours of 1/2-inch storm.
  - 3. Record and file with SWPPP.

### **3.06 CLEANUP AND RESTORATION**

- A. Remove temporary erosion control items when area is permanently stabilized and upon completion of Work.
- B. Restore all plant, equipment, or other supplementary operation sites to prevent siltation and erosion.
- C. Repair any off-site damage resulting from failure to install or maintain BMPs.
- D. Restore and stabilize areas disturbed during removal of erosion controls.

**END OF SECTION**